RAIL COACH FACTORY, KAPURTHALA

MD46111 Date: 15.09.2025

Sub: Corrigendum to Specification for Modular Toilets from Sheet Moulding Compound (SMC) MDTS_24401_Rev_1.
Ref :- CMT office letter no. C&M/R&P/25-26 Dt 12-09-2025

It is clarified that SN 10 of Clause 6.0 of Specification for Modular Toilets from Sheet Moulding Compound (SMC) MDTS_24401_Rev_1 may be read as mentioned below:

SN	Properties	Specified Value		Evaluation
		Existing	To be corrected to	
10	Fibre content by weight (w/w)-min (%)	25-30	25	1172 Method B/ASTM D3171

15.09.25

(Nitin Yadav)
Dy CME/Design-Fur

CDE/RCF:- May kindly approve

Dy CPLE-III

Dy CPLE-II

Copy to: -

CQM, CPLE, CWE/Fur, CMM/RCF, CMT, CMM/TKJ

SSE/Record

SSE/Lib/Design

SSE/Design/RCF/TKJ

E4268912
12/9/2025

RAIL COACH FACTORY,KAPURTHALA

Office of the
Chemist & Metallurgist
Date:-12/09/2025

NoC&M/R&P/25-26

Sub:-Clarification regarding % of fibre content in MDTS 24401 Rev.01.

The Fibre content mentioned in the table of MDTS 24401 Rev.01 of Para 6.0 at SN 10 by weight (w/w) as 25-30 % minimum. Clarification in this regard may be provided whether the range of fibre content is 25-30 % is required or minimum 25% or 30 % is required.

Please treat it most urgent as some inspection cases are under progress in M&C lab.

12/9/25
Chemist & Metallurgist

DyCME/Design Fur