RAIL COACH FACTORY, KAPURTHALA

MD35131 DATED: 29/01/2026

Sub: - Issue of corrigendum-1 of "TECHNICAL SPECIFICATION FOR FIRE RETARDANT RIGID FOAM" as per MDTS 44374 Rev-0 .

Following modifications are made in specification no. MDTS 44374 Rev-0.

S.No.	Clause	Earlier	Modified
1.	5.1	All the testing shall be conducted by NABL accredited Lab for that particular test. The fire retardant tests as per EN 45545 -2 shall be conducted by either NABL accredited Lab for these testes or Testing lab accredited as per ISO/IEC-17025 to perform/conduct fire test as per EN45545-2 (Proof of same shall be submitted).	All the testing form SN 1-9 of table 3 shall be conducted by NABL accredited Lab or ATIRA lab or DRDO, Pune or CIPET or any Govt. Labs. The fire retardant tests as per EN 45545 -2 shall be conducted by either NABL accredited Lab for these testes or Testing lab accredited as per ISO/IEC-17025 to perform/conduct fire test as per EN45545-2 (Proof of same shall be submitted).

31/01/26

DY.CME/DF

31/1/26

CDE /RCF :- May kindly approve

CME/QA, CPLE, CWE/FUR, CMM/HSQ, CWE/SHELL, DY.CME/LHB/HSQ

DY.CMM/G, CMT, DY.CPLE-II & III, DY.CMM/FUR

SSE/Filing section

SSE/LIB. Mech. Design

SSE/Record(with original copy)

SSE/Design/RCF/TKJ

Copy for information to:

DY.CME/D, Vendor/D Shell/D Bogie