Rail Coach Factory, Kapurthala

MD46291 Dated: as signed

Sub: Issue of corrigendum-1 to specification no. MDTS-24427 rev00 Schedule of Technical Specification for Emergency Panic Button For Divyangjan Lavatory of IR Coaches.

Following is corrigendum-1 to MDTS-24427 rev00 Schedule of Technical Specification for Emergency Panic Button for Divyangjan Lavatory of IR Coaches for information and necessary action at your end:

SL.NO	Clause	Earlier	**Modified**
1	Point no 08 of Design & Construction.	**Power supply interface** 24 VDC from coach auxiliary supply.	**Power Supply Availability** 110VAC/DC supply can be taken from LV panel of the coach. DC Supply varies from 77V DC to 138 V DC with 2% ripple
2	Point no 4 of Design and Construction	**Junction Box/Terminal Box** Aluminium of FRP enclosure, IP65 -DIN rail mounting terminal	**Mounting Accessories** Screws, clamps, gaskets, sealing rings, conduit glands etc and any other which is not mentioned but required for proper fitment shall be in scope of supplier
3	Warranty/Gurantee period	----	**New clause added.**

This has the approval of competent authority.

17/03/2

Dy CME/Design/Fur

CME/QA CPLE CWE/Fur CMM/HSQ CWE/Shell

Dy. CME/LHB/HSQ Dy. CMM/G CMT Dy. CPLE-II & III Dy. CMM/Fur

SSE/Filing Section

SSE/Library, Mech.

Design

SSE/Record

(Original copy)

SSE/Dev.

Copy for kind information to: