

RAIL COACH FACTORY, KAPURTHALA

The following item is not having STRs & requests have come for carrying out CCA of firms for this item for Gangway Bridge Mounting as per PL No. 33612717 (Drg No. 1 10113.0.24.120.001 . Detail list of infrastructure is given below:-

S No.	Description of infrastructure	REMARKS/ YES/NO
1	Separate covered area for storage of different grades of steel	--
2	Shearing machine of suitable capacity / CNC Laser / Plasma Profile cutting m/c	In house
3	Press brake of suitable capacity	In house
4	Hand grinder/handling equipments i.e. sling, hooks etc	In house
5	TIG/MIG welding with argon gas shielding	In house
6	Painting facilities	In house
7	Milling machine, Lathe, Drilling m/c	In house
9	Chemical testing: Tie up with NABL certified Lab	In house/Tie-up
10	Physical testing Lab: Firm should have in house or tie up with certified NABL lab for universal Testing Machine.	In house/Tie-up
11	Vernier Caliper, Measuring scale/tape, inside & outside micrometer	In house
12	The manufacturer shall have ISO-9001-2015 or latest certified	In house

May kindly permit use of above for assessing firm in CCA

Anshul
31/08/2022
SSE/FD

Dy CME/DP

31/08/22

CDE

Anshul
6/9/22