





**STR NO:RCF/ELECT/STR/0026-Rev-0 (2020)**

**SCHEDULE OF TECHNICAL REQUIREMENTS FOR  
BATTERY FUSE BOX (+VE & -VE) FOR LHB COACHES**

S. No.	Details of Amendments	Revision	Page No.	Reasons of Amendment
-	-	-	-	-

Approved by   
CEDE

RCF/EL/0026 Rev.-0 (2020)	11.11.2020			
STR no.	Date	SSE/Dev	SEE/D&D	Dy.CEE/D&D

**SCHEDULE OF TECHNICAL REQUIRMENTS FOR THE MANUFACTURING OF  
BATTERY FUSE BOXES (+VE & -VE) FOR LHB COACHES**

**1.0 Forward:**

This Schedule of Technical Requirements (STR) specify minimum essential Machinery, Plant and Testing Instruments required for manufacturing of **BATTERY FUSE BOXES (+VE & -VE)** for LHB type coaches and shall also be read in conjunction with the relevant Standards/Specifications /Drawings.




- 1.1 The firm should satisfy himself about having complied with the technical requirements of the Standards/Specification/Drawings and other Infrastructure, Testing Facilities requirement as per STR before applying for registration/assessment as per relevant STR.
- 1.2 The firm should have currently valid **ISO-9001** Certification including the subject item under its range of manufacture.
- 1.3 Firm is advised to regularly visit RCF website and get themselves updated on changes being made from time to time in STR/Specifications/Drawings.
- 1.4 Every Item shall be numbered /marked for identification traceability and analysis. The following details shall be imprinted on the number plate of each unit.
  - a) Serial Number
  - b) Year and month of manufacture, P.O. Reference
  - c) Name of the item
  - d) Name of firm

**2.0 FACILITIES:**

Information shall be furnished for of **BATTERY FUSE BOXES (+VE & -VE)** to relevant Standards/Specification/Drawings to no. **LW71001(latest) & LW71002 (latest)** as per details required in the following Annexure's:-

**2.1 ANNEXURE-I:**

It contains essential M&P infrastructure required for manufacture of **BATTERY FUSE BOXES (+VE & -VE)**. It however does not specify the capacity and quantity of the various items of equipment/components, the quantity/capacity of the M&P being dependent upon the manufacturing requirement. The firm should also have the facility for storing the Raw Material, Finished Product so as to maintain them in a healthy condition.

RCF/EL/0026 Rev.-0 (2020)	11.11.2020			
STR no.	Date	SSE/Dev	SEE/D&D	Dy.CEE/D&D

**2.2 ANNEXURE-II:**




It contains all Testing Facilities required. Record of calibration of all measuring apparatus shall be maintained and made available on demand.

**2.3 ANNEXURE-III:**

It contains Quality Assurance Plan for implementation by the firm. It will also be pre-requisite for a firm to submit QAP for according approval for supply of equipment. The major points, which are essentially required to be covered, shall be included therein.

**2.4 ANNEXURE-IV:**

It contains the requirements to be fulfilled for establishing the Credentials or the service network so that reliability of the equipment is ensured.

RCF/EL/0026 Rev.-0 (2020)	11.11.2020			
STR no.	Date	SSE/Dev	SEE/D&D	Dy.CEE/D&D

## 2.1 ANNEXURE-I




### DETAILS OF ESSENTIAL INFRASTRUCTURE

The following facilities/machinery and plant are considered essential for the manufacture of quality and reliable product.

- 1 CNC/Hydraulic Press Brake-100/120 Tons of suitable Bed Length. (Optional)
- 2 CNC Cutting and Shearing Machine. (Optional)
- 3 Grinding Machine.
- 4 Drilling Machine.
- 5 Buffing/Sanders.
- 6 Tig Welding Set.
- 7 Suitable Tools for Assembly.
- 8 Small Working Tools.
- 9 Cable Cutting and Dressing Tools.
- 10 Bench Vice.
- 11 Trolley for carrying material with in Workshop.
- 12 Working Tables.
- 13 Computer/Printer for Cable Markers.
- 14 Crimping Tools of adequate capacity.
- 15 Powder Coating Plant. (Optional)
- 16 Seven Tank Treatment Plant. (Optional)

#### Note:-

1. All the above facilities are considered **ESSENTIAL** at the Developmental Stage and shall be got verified by RCF representative before considering the firm as a Developmental Source. However facilities for "**OPTIONAL**" items can be "**OUTSOURCED**" from ISO certified manufacturer only.
2. An undertaking (MoU) along-with Valid ISO certificate, M & P details and QAP of the Sub Vendor with whom MoU made for the availability of "**OPTIONAL**" facilities shall be submitted duly Signed & Stamped.
3. RCF representative may visit the premises of such "**OUTSOURCED**" Sub vendor for Physical Verification compliance to the STR.

RCF/EL/0026 Rev.-0 (2020)	11.11.2020			
STR no.	Date	SSE/Dev	SEE/D&D	Dy.CEE/D&D

## 2.2 ANNEXURE-II




### ESSENTIAL MEASURING INSTRUMENTS FOR TESTING

The following instruments are considered necessary for testing purpose:-

1. H.V. Tester.
2. Megger (500/1000 volt DC).
3. Continuity Tester.
4. Milli-Voltmeter.
5. Regulated DC Source (0-200V DC).
6. Vernier Caliper (0-150 mm).
7. Micro-Meter.
8. Steel Scales.
9. Coating Thickness Gauge.
10. Digital Multimeter.
11. Test Panel having Voltmeter, Ammeter, Wattmeter, Frequency Meter and Power Factor Meter AC supply.
12. Testing Facility for IP test (Water Proofness) (**Optional**).
13. Tensile Tester (for Crimping Sockets).
14. Set-up for Load Testing.

#### NOTE:

- 1). All the above facilities are considered “**ESSENTIAL**” at the developmental stage and shall be verified by RCF representative before considering the firm as a developmental source.
- 2). THE OPTIONAL TESTING FACILITIES MENTIONED ABOVE CAN BE “**OUTSOURCED**” FROM A GOVT./NABL ACCREDITED LAB FOR TESTING PURPOSE.

RCF/EL/0026 Rev.-0 (2020)	11.11.2020			
STR no.	Date	SSE/Dev	SEE/D&D	Dy.CEE/D&D

## 2.3 ANNEXURE-III :

### QUALITY ASSURANCE PLAN (QAP)

The QAP shall be got approved from RCF and proper record shall be maintained.

#### 1. Organization:-

The firm shall submit the Organizational Chart along with the Qualification and Experience of key persons in management involved in Quality Assurance Programme. Being a manpower intensive job the following technical staff must be employed during developmental stage:

- ITI with min. **02** years experience or non ITI with min. **05** years experience.
- Supervisors staff with min. graduate in Electrical Engg. with 02 years experience or diploma holder in Electrical discipline with min. 05 years experience.

#### 2. Documentation:-

The manufacturer shall maintain all necessary documents and data that will help him to have consistency in producing quality product.

#### 3. Purchase of Raw Material:-




Raw Material/equipment shall be procured only from well proven/approved sources conforming to the relevant Standards/Specifications/Drawings. The critical components shall be procured from ISO-9001 certified vendors only.

#### 4. Quality Control Process:-

Screening of critical components shall be carried out In Process Inspection as a Quality Control Measure.

#### 5. Inspection and Testing:

- (i) **Receiving Material:** The manufacturer shall ensure that incoming material is not used for processing until it has been inspected or otherwise verified as conforming to the Specified requirements. Verification shall be in accordance with Quality Plan or laid down Documented Procedures.

RCF/EL/0026 Rev.-0 (2020)	11.11.2020			
STR no.	Date	SSE/Dev	SEE/D&D	Dy.CEE/D&D

- (ii) **In Process Inspection and Testing:** Inspect, Test and Identify Product as required by the Quality Assurance Plan or Documented Procedures evolved on the basis of RCF Specification (the latest) and other relevant Specification/Standards.
- (iii) The supplier shall carryout all final tests and inspection in accordance with the quality plan or documented procedures evolved on the basis of RCF specification and specified standard to complete the evidence of conformance of the Finished Product.

**6. Testing /Measuring Instruments:-**

The instrument and equipment used for testing and inspection shall be of the required accuracy and shall have valid **calibration certificate from Govt./NABL certified lab**. The Calibration Record should be maintained and shall be produced at the time of inspection & shall be included in QAP document/Test Reports.

**7. R&D Organization:**

The firm shall indicate the organizational structure of their R&D wing along with qualification of the personnel. Firm should have at least one Engineering Graduate, R&D Engineer with experience of more than 05(five) years in the field of Electrical/Mechanical/Chemical/Polymer Engineering.

**8. Laboratory Test House:-**




The manufacturer shall have adequate Testing Facilities to carry out various tests on the Raw Material, Stage Inspection and inspection of the Finished Product.

**9. Quality Audit:**

The manufacturer shall regularly send the sample for testing in recognized National Testing Institutions/NABL Approved Labs for counter checking the characteristics and to ensure quality level of their product.

**10. Handling/Storage/Delivery:**

The manufacturer shall have proper and adequate facilities for Handling & Storage of Raw Material and Finished Product. The supplier shall control, packing presentation including compliance of FIFO (First In First Out) and marking process so as to ensure conformity to the Railway requirements.




RCF/EL/0026 Rev.-0 (2020)	11.11.2020			
STR no.	Date	SSE/Dev	SEE/D&D	Dy.CEE/D&D

## 2.4 ANNEXURE-IV

### REQUIREMENTS FOR ESTABLISHING THE CREDENTIAL

It contains the requirement to be fulfilled for stabilizing the Credentials so that Reliability of the Product/ Equipment is ensured.

1. The firm should have capability to attend failures at RCF and at Zonal Railways/Field Units of each Region widely spread across the Country with positioning of Qualified, experienced team of Engineers with minimum of 05 years experience in Electrical Engineering should be available so that they can investigate/attend the reported failures within the specified time limits as “**IS ON WHERE BASIS**” in the Zonal Railways/ Depots/ Field Units.

RCF/EL/0026 Rev.-0 (2020)	11.11.2020			
STR no.	Date	SSE/Dev	SEE/D&D	Dy.CEE/D&D